

Phase coherence in quasicondensate experiments: an *ab initio* analysis via the stochastic Gross-Pitaevskii equation

D. Gallucci, S. P. Cockburn, and N. P. Proukakis

Joint Quantum Centre (JQC) Durham-Newcastle, School of Mathematics and Statistics,
Newcastle University, Newcastle upon Tyne, NE1 7RU, United Kingdom

We perform an *ab initio* analysis of the temperature dependence of the phase coherence length of finite temperature, quasi-one-dimensional Bose gases measured in the experiments of Richard *et al.* (Phys. Rev. Lett. **91**, 010405 (2003)) and Hugbart *et al.* (Eur. Phys. J. D **35**, 155-163 (2005)), finding very good agreement across the entire observed temperature range ($0.8 < T/T_\phi < 28$). Our analysis is based on the one-dimensional stochastic Gross-Pitaevskii equation, modified to self-consistently account for transverse, quasi-one-dimensional effects, thus making it a valid model in the regime $\mu \sim \text{few } \hbar\omega_\perp$. We also numerically implement an alternative identification of T_ϕ , based on direct analysis of the distribution of phases in a stochastic treatment.

PACS numbers: 67.85.-d, 67.85.Bc, 03.75.Hh

I. INTRODUCTION

Weakly interacting ultracold Bose gases are of great interest because they allow the ‘pure’ study of quantum phenomena on a macroscopic scale. Such systems are typically engineered in harmonic traps with different geometric configurations, whose dimensionality plays a crucial role in determining the properties of these gases. In three-dimensional harmonic traps, the system undergoes a phase transition which leads to the appearance of coherence across the entire sample, as demonstrated in [1–4]. By setting the trap frequency in one direction to be much larger than the others, the effective system dynamics is reduced to two dimensions [5–8], with many interesting phenomena occurring, such as the Berezinskii-Kosterlitz-Thouless transition [9–16]. Increasing the trap frequency in a further direction allows the realization of highly elongated traps, where the interesting physics occurs in the axial direction [5, 17–23].

In such a regime two characteristic temperatures become relevant, associated with the onset of phase (T_ϕ) and density (T_d) fluctuations [24]. For temperatures $T_\phi < T < T_d$, density fluctuations tend to be suppressed, and the system reduces to a condensate with fluctuating phase (quasicondensate) [25]. In such a geometry low-energy thermal excitations of the axial modes play a crucial role, as they tend to destroy the coherence in the sample [24–40]; such excitations may have wavelengths greater than the transverse extent of the system, therefore acquiring a one-dimensional (1D) character [19–22, 36–49]. An accurate analysis of the coherence properties in such systems is therefore necessary for potential applications, such as matter-wave interferometry [41, 50–55], atom chips [56] and atom lasers [2, 57–60]. Although experiments can nowadays be engineered to produce gases which are both weakly interacting and practically 1D ($\mu, k_B T \lesssim \hbar\omega_\perp$, where μ is the chemical potential, $k_B T$ the thermal energy and $\hbar\omega_\perp$ the transverse excitation energy) [23, 41–49], the early experiments performed did not satisfy these conditions so well,

and the system was instead in the 1D-3D crossover regime [17, 19–22, 36–40].

In this work we propose and implement a modified stochastic model which enables us to perform a successful *ab initio* description in the ‘intermediate’ regime $\mu, k_B T \sim \text{few } \hbar\omega_\perp$ where quasi-condensate physics dominates, but transverse effects still need to be appropriately accounted for. More specifically, we analyze two early experiments [22, 40] investigating the phase coherence properties of weakly interacting, quasi-1D Bose gases. These experiments measured the temperature dependence of the coherence length L_c , over which the gas maintains an appreciable coherence, both in the ‘strong’ ($6 < T/T_\phi < 28$) [22] and ‘weak’ ($0.8 < T/T_\phi < 8$) [40] phase fluctuation regimes. Although it is theoretically anticipated (for a homogeneous gas [61]), that the coherence length, scaled to the experimental half-length of the system L , should yield a universal curve when plotted against the reduced temperature T/T_ϕ , it would not actually be appropriate to incorporate their *reported* data into a single graph [62] spanning the entire regime $0.8 < T/T_\phi < 28$, because the two experiments used different techniques to extract the coherence.

The main achievements of this work are as follows: (i) we show that the measurements reported in both experiments are indeed *consistent* with such a unified curve; this is achieved by a completely *ab initio* analysis of the experimental data, using only the quoted experimental values for atom number, trap frequencies and temperature; (ii) our analysis, which is based on the quasi-1d stochastic Gross-Pitaevskii equation [63], appropriately modified here to extend its validity to the regime $\mu \sim \text{few } \hbar\omega_\perp$ reveals excellent agreement in the ‘strong’ phase fluctuation regime; (iii) our attempt to more closely mimic the experimental procedure of [40] – whose findings have not been adequately interpreted to date – also yields good overall agreement (within error bars); in order to further improve this we implement an alternative approach of extracting a phase coherence temperature based on direct analysis of the phase distri-

butions from different realisations of our stochastic treatment.

II. METHODOLOGY

Our treatment is based on a modified one-dimensional form [63] of the stochastic Gross–Pitaevskii equation (SGPE) [64–66]. The modification proposed in [63] – which was found to be essential to accurately simultaneously reproduce both *in situ* density profiles and density fluctuations of recent quasi-one-dimensional experiments [42, 45, 49] – takes the form:

$$i\hbar \frac{\partial \psi(z, t)}{\partial t} = [1 - i\gamma(z, t)] \left(-\frac{\hbar^2}{2m} \frac{\partial^2}{\partial z^2} + V(z) + \hbar\omega_{\perp} [\sqrt{1 + 4|\psi|^2 a_s} - 1] - \mu \right) \psi(z, t) + \eta(z, t). \quad (1)$$

Here ψ describes the relevant (highly populated) low-energy modes of the system, $V(z) = m\omega_z^2 z^2/2$ is the axial trapping potential and η is a complex Gaussian noise term, with correlations $\langle \eta^*(z, t) \eta(z', t') \rangle = 2\hbar\gamma(z, t) k_B T \delta(z - z') \delta(t - t')$, where $\gamma(z, t)$ denotes the dissipation. (For further details on numerical implementations and related treatments see Refs. [28, 63–80]). The condition $\mu \lesssim \text{few } \hbar\omega_{\perp}$ can lead to a swelling of the condensate in the transverse direction, relative to the true 1D transverse ground state; this quasi-1D effect is due to repulsive interactions and is reproduced by using the modified nonlinear term $\hbar\omega_{\perp} [\sqrt{1 + 4|\psi|^2 a_s} - 1]$ (where a_s is the s-wave scattering length), which reduces to the 1D result in the limit $4|\psi|^2 a_s \ll 1$. For the ordinary Gross–Pitaevskii equation, this was shown in Refs. [34, 81–84], and its validity was verified experimentally in [48].

In order to match to experimental atom numbers, it is crucial to also include in our treatment the contribution (n_{\perp}) to the linear density profile of transverse thermal atoms with energy greater than $\hbar\omega_{\perp}$. This is done via

$$n(z; \mu, T) = \langle |\psi(z; \mu, T)|^2 \rangle + n_{\perp}(z; \mu, T) \quad (2)$$

where $\langle \dots \rangle$ denotes ensemble averaging, obtained by averaging over many different realizations of the noise, and

$$n_{\perp}(z; \mu, T) = \frac{1}{\lambda_{dB}} \sum_{j=1}^{\infty} (j+1) g_{1/2} \left(e^{\mu_j(z)/k_B T} \right) \quad (3)$$

where $g_{1/2}(\dots)$ is the polylogarithm (or Bose function) of order 1/2, and $\lambda_{dB} = h/\sqrt{2\pi m k_B T}$ is the thermal de Broglie wavelength [85]. While in the limit $\mu < \hbar\omega_{\perp}$ studied in our previous work [63], it is sufficiently accurate to use $\mu_j(z) = \mu - V(z) - j\hbar\omega_{\perp}$ in Eq. (3) (see also [45, 86]), the effect of mean-field potential experienced by the transverse thermal atoms should also be taken into account in the regime $\mu > \hbar\omega_{\perp}$, characteristic of the experiments of Refs. [22, 40] studied here. For this reason we use here the modified expression:

$$\mu_j(z) = \mu - V(z) - j\hbar\omega_{\perp} - 2g(\langle |\psi|^2 \rangle + n_{\perp}) \quad (4)$$

where $g = 2a_s \hbar\omega_{\perp}$ is the effective interaction strength.

In the following sections we systematically use Eqs. (1)–(4) to match to the experimental atom number (noting also that the profiles generated by Eq. (2) correspond to transversely *integrated* density profiles, typical of ultracold gas experiments), before performing an analysis of the coherence properties.

For both experiments analysed here, the *only* experimental inputs to our theory are the atomic species used (^{87}Rb in both cases), the trapping configuration, the temperature and atom number corresponding to *each reported experimental data point* [87]. In our *ab initio* analysis we fix experimental trap configuration and temperature, and vary μ until the desired number of atoms is reached in our simulations. Depending on the available experimental data, we either match to the *total* or the *quasicondensate* experimental atom number, as explained in each case. Representative error bars are also calculated for our simulations, based on variations in both number and temperature, in close analogy to the experimental analysis.

In order to discuss both experiments in a coordinated way, and demonstrate their consistency, we consider the dependence of the coherence length on temperature, with both parameters appropriately scaled to show the emergence of universal physics. In performing this analysis, we also address experiment-specific features, meaning the precise definitions of the coherence length and phase fluctuation temperature differ slightly within our subsequent analysis, however this difference is clearly labelled within figures.

III. COMPARISON TO THE EXPERIMENT OF RICHARD ET AL. [22]

The first experiment we consider is that of Richard *et al.* [22], in which a very elongated harmonic trap ($\omega_{\perp}/2\pi = 760$ Hz and $\omega_z/2\pi = 5$ Hz) was used to generate quasicondensates of atom numbers in the range $0.25 \times 10^5 - 0.65 \times 10^5$ and at temperatures $90 \text{ nK} \leq T \leq 350 \text{ nK}$. These parameters enabled the ‘strong’ phase fluctuation regime $6 < T/T_{\phi} < 28$ to be probed.

In order to investigate the phase coherence properties of the gas, the axial momentum distribution was measured by means of Bragg spectroscopy and found to have a Lorentzian shape, consistent with an exponential decay of the correlation function in space anticipated in the regime of large phase fluctuations [21, 22, 36, 38]. This approach enabled the coherence length L_c to be extracted from the half width at half maximum of the momentum profile, and its temperature dependence to be measured. Using the original data relevant for Ref. [22] (see also [39] and [88]), we can plot this in universal form by scaling the coherence length L_c to the half-length of the condensate L , and plotting against the reduced temperature T/T_{ϕ} . Here we use the general definition of T_{ϕ} in terms of the 1D axial quasicondensate peak density, $n_{qc}(0)$, i.e.




Figure 1. (Color online) Coherence length L_c scaled to the half length of the quasicondensate L vs. reduced temperature T/T_ϕ . Comparison of experimental data [22, 39] spanning the range $T/T_\phi > 6$ (hollow red triangles) to the SGPE model (upward filled black triangles). Additional numerical results generated with the SGPE model for lower temperatures $T/T_\phi < 6$ are also shown (downward filled black triangles), together with the best fit of the SGPE results (dot-dashed black line). The horizontal experimental error bar is taken as 10% [22], based on typical experimental uncertainties, while the corresponding error in the simulated point arises from a typical 15% variation in the quasicondensate atom number and 5% variation in temperature [22]; in both cases the vertical error bars fall within the symbol size. Temperatures have been scaled to $T_\phi[n_{qc}(0)] = \hbar^2 n_{qc}(0)/mk_B L$, where $n_{qc}(0)$ is the peak quasicondensate density; in the SGPE analysis, the spatial extent of the quasicondensate is obtained *ab initio* as the temperature dependent Thomas-Fermi radius $R_{TF}(T)$ [89].

[17, 34]

$$T_\phi[n_{qc}(0)] = \hbar^2 n_{qc}(0)/mk_B L, \quad (5)$$

which is relevant for Refs. [22, 39]. (See discussion following Eq. (7) for a closely related expression valid in the Thomas-Fermi regime and used in the analysis of Ref. [40].)

In order to simulate the experiment, we compute the first order correlation function in position space $g^{(1)}(-z/2, z/2) = \langle \psi^*(-z/2)\psi(z/2) \rangle$ (normalized to the averaged central density $\langle |\psi(0)|^2 \rangle$), finding an exponential behaviour against distance z as in the experiment (since $T \gg T_\phi$ here). We then compute the Fourier transform $C^{(1)} = F[g^{(1)}]$ and extract the coherence length L_c by measuring Δk , the half-width at half maximum of $C^{(1)}$. We also use our simulated results to find $T_\phi[n_{qc}(0)]$, with the required inputs being the quasicondensate peak density and spatial extent of the gas, each of which we obtain *ab initio*. Specifically, the quasicondensate density is extracted as [74, 90–92]:

$$n_{qc}(z) = \sqrt{2\langle |\psi(z)|^2 \rangle^2 - \langle |\psi(z)|^4 \rangle} \quad (6)$$

and its peak value is used in the expression for $T_\phi[n_{qc}(0)]$. Moreover, the half-length of the quasicondensate in our simulations is given by a temperature dependent Thomas-Fermi radius $R_{TF}(T)$, extracted from Eq. (1) analogously to the procedure used in the modified Popov theory (see [27, 28, 91] and [89]).

Our *ab initio* SGPE results presented in Figure 1 (upward filled black triangles) show excellent agreement to the experimental results (hollow red triangles) in this ‘strong’ phase fluctuation regime within their respective characteristic error bars (see caption for details). Note that the coherence length is smaller than the quasicondensate extent ($L_c/L < 1$) in the temperature range probed here, illustrating the fundamental role of phase fluctuations in such an elongated geometry. As T/T_ϕ approaches zero, we expect the coherence length to increase: to show this, we have generated a further set of numerical points for $T/T_\phi < 6$ (downward filled black triangles), which indeed confirm this picture, and the ‘universal nature’ of such a scaled diagram.

In the following section, we turn to the investigation of the experiment of Hugbart et al. [40], in which the regime $T/T_\phi < 8$ was probed using different methods.

IV. COMPARISON TO THE EXPERIMENT OF HUGBART ET AL. [40]

The Bragg spectroscopy method used in the previous experiment limited accurate investigations of the coherence properties of the gas to $T/T_\phi > 6$, as at lower temperatures the width of the momentum distribution of the gas was no longer easily resolved [39]. In the experiment described in [40], an alternative interferometry technique (see also Ref. [21]) was used to measure the spatial correlation function in the regime $0.8 < T/T_\phi < 8$.

In particular, after the condensate was released, two Bragg pulses were applied, playing the role of matter-wave beam splitters. The contrast of the resulting interference fringes was then obtained from the modulus of the Fourier transform of the interference pattern, and the coherence length was extracted from the decrease of the contrast as a function of the distance between the two interfering condensates. The experimental data (hollow red circles of Fig. 2), show that, in the regime $T \simeq T_\phi$, the coherence extends over more than half of the system size.

In order to access such low values of T/T_ϕ , it was technically easier to use slightly *less* elongated traps than in [22]. In fact, two different trap configurations were used (first: $\omega_\perp/2\pi = 395$ Hz and $\omega_z/2\pi = 8.67$ Hz; second: $\omega_\perp/2\pi = 655$ Hz and $\omega_z/2\pi = 6.55$ Hz); the data obtained with the second trap were subdivided into two different blocks, characterised by two different values of the evaporation parameter, which proved necessary in order to vary T/T_ϕ , while keeping the condensed fraction fairly constant within each data block. The *total* atom numbers measured in this experiment were found to lie




Figure 2. (Color online) Scaled coherence length L_c/L vs. reduced temperature T/T_ϕ . Comparison of experimental data [40] (hollow red circles) to predictions of the SGPE model (filled black squares). The reported experimental best fit (dashed red line) and the theory used in [40] to interpret the experimental data (solid line) are also shown, alongside the SGPE fit from Fig. 1 (dot-dashed black line). Typical error bars for corresponding data points in both experiment and SGPE model are indicated, with the SGPE ones arising from a characteristic 20% variation in total atom number and an additional 5% variation in temperature; (note that the SGPE error bars for the point with $T/T_\phi \approx 1.2$ lie within the point size and are not visible). The SGPE results are scaled to $T_\phi[n_{qc}(0)]$ for consistency with the discussion of Fig. 1.

in the range $0.8 \times 10^5 - 3 \times 10^5$ (corresponding quasicondensate [93] atom numbers: $0.5 \times 10^5 - 2.5 \times 10^5$), within a temperature region of 100 – 230 nK [87].

In our simulations, rather than reproducing the experimental procedure, for which non-equilibrium expansion dynamics would need to be accounted for, we *initially* instead extract the corresponding *in situ* coherence length by adopting the *same* methodology described in Section III. This is done here in order to firstly explore whether our results for this new system also lie on the same ‘universal’ curve as those of Ref. [22] (dot-dashed black curve of Fig. 1) when analysed in an identical manner.

We indeed find that the new numerical results generated in this regime $T \sim \text{few } T_\phi$ (filled black squares of Fig. 2) lie on the same (dot-dashed black) curve provided by the fit in Fig. 1; this demonstrates the universal character of the coherence properties, as numerical results obtained with different sets of trap configurations, temperatures and atom numbers yield the same behaviour. As the analysis of Ref. [40] reported error bars for two indicative data points, we repeat a similar analysis within the SGPE theory – in which case it is based on a 20% variation in total atom number [94], and a typical 5% variation in temperature [95, 96].

However, while our methodology led to a unified theoretical graph over both the ‘weak’ and ‘strong’ phase fluctuation regime, which also provides excellent agreement with the experiment [22] for $T > 6T_\phi$, the corresponding SGPE results for the experiment of Ref. [40] differ from the experimentally-reported ones. The reason for this discrepancy is twofold: firstly, in [40] it is an ‘effective’ correlation function that is evaluated, which leads to a different definition of the coherence length [62] (see Section IV A); secondly, the theoretical values of T/T_ϕ obtained in our treatment do not span precisely the same range as in the experiment (see Section IV B).

With regard to the latter point, we note that the analysis of Ref. [40] was actually based on a *slightly* modified definition for T_ϕ compared to that of Eq. (5); in particular, in [40], T_ϕ was defined in terms of the *number* of quasicondensate [93] atoms N_{qc} (and not on the peak quasicondensate *density*), via the expression [97]

$$T_\phi[N_{qc}] = 15\hbar^2 N_{qc}/16mk_B L^2. \quad (7)$$

This is in fact a simplified form of Eq. (5), valid for 3D condensates [98] (i.e. condensates where the transverse density profiles can be well approximated by a Thomas-Fermi profile).

In the following sections, we further investigate potential sources of discrepancy between our simulations and the experimental results of Ref. [40], focusing our analysis on a modified effective correlation function defined below, as relevant for this experiment. Throughout our analysis, the coherence length is always referred to as L_c , with the method of its extraction clearly identified in each figure.

A. Effective correlation function

The main source of the observed discrepancy should be related to the experimental measurement of an ‘effective’ correlation function (see Eq. (9) in [40]), instead of the correlation $C^{(1)}$ measured in Richard *et al.* [22] and discussed thus far. In the experiment of Ref. [40], this effective correlation was introduced in order to cancel the random phase caused by the shot to shot fluctuations of the global position of the contrast fringes; it was found that taking the absolute value of the Fourier transform of the fringe pattern before averaging achieved this aim (for a more detailed explanation see Section 4.2 in Ref. [40]), but modified the coherence length relative to that of $C^{(1)}$. For this reason, we should not expect the measurements from the two experiments to lie on the same curve, as they measure two different quantities [62].

In analogy to the experimental method used to extract the coherence length, we implement this feature by taking the absolute value of the Fourier transform of $g^{(1)}$ from *each individual run*, before averaging over the different realizations of the noise; our ‘effective’ correlation function, which we here call $C^{(1,\text{mod})}$, takes the form $C^{(1,\text{mod})} = \langle |F[g^{(1)}(-z/2, z/2)]| \rangle$. The ‘effective’

correlation function is found to have similar behaviour to $C^{(1)}$, but it decays faster (in the region of interest) in momentum space, thus resulting in larger values of the coherence length. This is shown in Fig. 3, which compares the theoretical results to the experimental measurements using $C^{(1)}$ (brown filled squares) and $C^{(1,\text{mod})}$ (blue filled circles). Although we consciously do not exactly reproduce the experimental measurement sequence, the results obtained from the SGPE analysis of the ‘effective’ correlation function clearly show a very similar trend to the experimental findings over the probed regime; in particular, they tend to lie on the reported line of best fit of the experimental data (dashed red line). We note that our calculation of $C^{(1,\text{mod})}$ leads to a much improved agreement with the experimental data than the original theoretical analysis reported in [40] (solid red line) which largely overestimates the amount of coherence in the system.




Figure 3. (Color online) Scaled coherence length L_c/L vs. reduced temperature T/T_ϕ . Comparison of numerical SGPE findings extracted via $C^{(1,\text{mod})}$ (filled blue circles) and via $C^{(1)}$ (filled brown squares) against experimental data points of Ref. [40] (hollow red circles). The theory used in [40] is also shown (solid line) together with the experimental best fit (dashed red line). SGPE numerical points are scaled to $T_\phi[N_{\text{qc}}]$, and respective error bars account for 20% variation in total atom number and a further 5% variation in temperature. Inset: comparison of SGPE results, in which temperatures are scaled to the *experimentally quoted* values of T_ϕ . SGPE results shown in the inset are obtained by matching either the *total* number of atoms (blue filled circles, main figure and inset), or the *quasicondensate* atom number (green crosses, inset only).

Although the experimental results and our simulated points (extracted via $C^{(1,\text{mod})}$) demonstrate very good agreement when accounting for their respective error bars, the experimental data still appear to systematically extend to slightly larger values of T/T_ϕ , as visible

in Fig. 3. This could be attributed either to a systematic shift in the experimental determination of T (e.g. arising in expansion imaging), which however increases with increasing T/T_ϕ ratio, or to the method by which the inputs to T_ϕ are extracted in the analysis. In the rest of the paper we assume that this shift arises solely from the latter and attempt to further improve on the spanned range of T/T_ϕ .

B. Identification of T_ϕ

A given set of trap frequencies, temperatures and total atom numbers should fix the characteristic temperature T_ϕ to a particular value which is the same between theory and experiment; for this reason, in order to attempt to span precisely the same *range* of T/T_ϕ as in the experiments, we plot in the *inset* of Fig. 3 our theoretically-obtained values for the reduced coherence length L_c/L versus T/T_ϕ using here the *experimentally*-obtained values for T_ϕ . This still reveals good agreement between our theoretical findings (blue filled circles) and the experimentally-extracted ones (hollow red circles), within the reported experimental error bars.

We have also performed a separate analysis, based again on the SGPE but in which we instead match our numerically extracted *quasicondensate* number to the corresponding experimentally-extracted ‘condensate’ number [87], and measure the coherence length via $C^{(1,\text{mod})}$. These closely related measurements are shown in the inset of Fig. 3 with green crosses; we find good overall agreement both with the experimental findings (hollow red circles) and with the previous analysis, based on matching the experimental total atom number instead (filled blue circles).

In order to further resolve the remaining discrepancy between theory and experiment in the regimes of T/T_ϕ analysed, in the next section we discuss an alternative method to extract T_ϕ from the SGPE simulations.

1. T_ϕ extracted from the phase distribution

In this section we investigate an alternative method of reproducing the experimental results of Ref. [40] from an SGPE analysis. Our approach is motivated from footnote 47 of [40], stating that T_ϕ can be obtained from the relation $L_\phi/L = T_\phi/T$ [17] with L_ϕ identified as the characteristic separation over which the phase fluctuates by 1 radian at the trap centre.

In order to extract values for T_ϕ according to the relation described above, we take here the approach of systematically analysing the phase distributions of the ensemble of stochastic fields ψ at several distances from the trap centre. Within the Thomas-Fermi radius, we find these distributions to be well fitted with Gaussian functions, whose standard deviation increases with increasing distance from the trap centre due to the enhanced role of

thermal fluctuations (see Fig. 5 in Appendix A and related work in [47]). In this analysis, L_ϕ can be identified as the distance from the centre where the standard deviation of the Gaussian fit to the phase distribution reaches a particular value. Our analysis indicates that when this (free) parameter takes the value of $\sigma = 0.65$, optimum agreement with the experimental findings is obtained regarding the spanned range of T/T_ϕ .




Figure 4. (Color online) Scaled coherence length vs. reduced temperature. Experimental data [40] (hollow red circles) against numerical SGPE results extracted via $C^{(1,mod)}$ (blue stars); in the SGPE analysis temperatures are scaled to T_ϕ extracted from the phase distribution (see Appendix A). The theory used in [40] is also shown (solid line) together with the reported experimental best fit (dashed red line). Error bars account for 20% variation in total atom number (solid blue line) and 8% variation in the standard deviation (dashed blue line) (see Appendix A).

The simulated results, with temperatures scaled to T_ϕ extracted as described above (blue stars), are shown in Fig. 4, alongside the experimental findings (hollow red circles). We also include here error bars for the previously considered indicative data points (as in Ref. [40]). In obtaining these we consider here two sources of error: firstly, as in previous figures, a variation in total atom number of 20% [94]; secondly, as the horizontal axis is also sensitive to the precise value of σ chosen, the sensitivity to a variation in σ of ± 0.05 is shown by the additional dashed portions of the error bars.

V. CONCLUSIONS

An *ab initio* model capable of capturing the phase coherence properties of highly-elongated, weakly-interacting Bose gases is of fundamental importance for future applications such as atom-interferometers and atom lasers. In this work we have analysed one such

model, the stochastic Gross-Pitaevskii equation (SGPE), with novel and self-consistent modifications in order to take account of quasi-one-dimensional effects. Comparing to the experiment of Richard *et al.*, Ref. [22], which considered the regime of relatively strong phase fluctuations $T/T_\phi > 6$, we found excellent agreement between experiment and the SGPE theory, based solely on using the experimental parameters (i.e. trap configurations, atom number, temperatures) as inputs for the theory.

We further compared the SGPE theory to the findings of Hugbart *et al.*, Ref. [40] for the opposite low temperature regime $T \lesssim \text{few } T_\phi$, which is more challenging to probe in experiments. While the SGPE analysis gave a temperature dependence of the coherence length in quantitative agreement with the experimental trend (within error bars), undertaking a point-by-point analysis of the experimental data was found to span a slightly narrower range of T/T_ϕ than the experimentally-reported curve, indicating a systematic deviation. We argued that this discrepancy may arise as a result of the different identifications of T_ϕ between theory and experiment, possibly due to the different means of processing the ‘raw’ experimental data and stochastic numerical results, e.g. due to differences in extracting the quasicondensate atom number which then feeds into the expression for T_ϕ .

We have partially examined this issue by using instead a phase sensitive means of extracting T_ϕ from characterisation of the ensemble phase distribution in SGPE simulations. In particular, motivated by footnote 47 of Ref. [40], we identified T_ϕ through the relation $T_\phi = T(L_\phi/R_{TF}(T))$ where L_ϕ was chosen as the characteristic separation from the trap centre at which the phase distribution is fitted by a Gaussian with a particular value for the standard deviation. In our treatment however this value is a free parameter chosen here so as to match the experimental range of T/T_ϕ .

Finally, as the measurements performed in [40] rely on an interferometric technique, this opens up a way to indirectly ‘extract’ the Penrose-Onsager mode in a quasi-one-dimensional experiment solely from knowledge of density and the two lowest equal-time correlation functions, with the Penrose-Onsager condensate mode density emerging as the phase- and density-fluctuation suppressed part of the density via $n_{PO}(z) \approx n(z) \sqrt{2 - g^{(2)}(z)} g^{(1)}(0, z)$ [28, 74].

VI. ACKNOWLEDGMENTS

We acknowledge the group of Alain Aspect (in particular: Jocelyn Retter for providing us their data in 2005 and Mathilde Hugbart for recent clarifications), Fabrice Gerbier and Joseph Thywissen for comments specific to this manuscript and Mike Garrett for discussions. Funding was provided by the UK EPSRC (Grant No. EP/F055935/1).

Appendix A: Analysis of the phase distribution

The numerical procedure implementing the SGPE model makes use of the Condor system [99], which is a mechanism to run parallel simulations, on different machines. Using this method we generate a large number of




Figure 5. Distribution of the phase of $a_c^* \psi(z)/|a_c|$ (where a_c is the amplitude of the Penrose-Onsager mode), for a chosen temperature $T \approx T_\phi$ (left point with error bars in Figs. 2-4), at different locations from the trap centre. Shown are the distributions at the condensate edge (left plot), at the point $z = L_\phi$ (central plot) where the distribution is fitted by a Gaussian (illustrated by the red solid curve) of standard deviation $\sigma = 0.65$ (which for the particular numerical point considered occurs at $z \simeq 0.5 R_{TF}(T)$) and at the trap centre $z = 0$ (right plot). The distributions are centered and normalised, and the phase ϕ is scaled to π .

stochastic realizations of the wavefunction ψ (typically ~ 1000 in a very short time); in this way we can then extract physical observables by performing the average over the ensemble of stochastic trajectories. In each numerical realization, which is somewhat analogous to an individual experimental run, the phase of the wavefunction ψ takes on a certain value at each position, leading to a distribution across the ensemble; it is then interesting to investigate how the distribution of the several realizations of the phase changes with the distance from the trap centre, at a definite value of T/T_ϕ .

In Fig. 5 we report phase histograms of the stochastic field $\psi(z)$, locked to the phase of the Penrose-Onsager (condensate) mode ϕ_c [74, 100], at three values of the distance from the trap centre, for the experimental data point with $T \approx T_\phi$ (left point with error bar in Figs. 2-4). To be more specific, we plot the phase of $a_c^* \psi(z)/|a_c|$, where a_c is the amplitude of the Penrose-Onsager mode, given by $a_c = \Delta z \sum_{z_i} \phi_c^*(z_i) \psi(z_i)$, where Δz is the grid spacing (see [74, 100] for further details and implementation).

The broadness of the generated distributions is an indication of the amount of coherence at a specific spatial point in the system: we expect the distribution to become broader with increasing distance from the trap centre, and be almost flat at the edge, where the system becomes purely thermal (Fig. 5). We define L_ϕ to be the distance at which the phase histogram is well fitted by a Gaussian with a particular value of the standard deviation σ . Following such a procedure, we can then define a phase fluctuation temperature T_ϕ from the relation $T_\phi \approx T(L_\phi/R_{TF}(T))$ [17, 24]. The standard deviation is here a free parameter, and we find that the value of $\sigma = 0.65 \pm 0.05$ provides very good matching to the experimental data, as shown in Fig. 4 (with corresponding range $z = L_\phi \sim (0.15 - 0.6) R_{TF}(T)$ for this chosen value of σ).

-
- [1] M. R. Andrews, C. G. Townsend, H.-J. Miesner, D. S. Durfee, D. M. Kurn, and W. Ketterle, *Science* **275**, 637 (1997)
 - [2] E. W. Hagley, L. Deng, M. Kozuma, M. Trippenbach, Y. B. Band, M. Edwards, M. Doery, P. S. Julienne, K. Helmerson, S. L. Rolston, and W. D. Phillips, *Phys. Rev. Lett.* **83**, 3112 (1999)
 - [3] J. Stenger, S. Inouye, A. P. Chikkatur, D. M. Stamper-Kurn, D. E. Pritchard, and W. Ketterle, *Phys. Rev. Lett.* **82**, 4569 (1999)
 - [4] I. Bloch, T. W. Hansch, and T. Esslinger, *Nature (London)* **403**, 166 (2000)
 - [5] A. Görlitz, J. M. Vogels, A. E. Leanhardt, C. Raman, T. L. Gustavson, J. R. Abo-Shaeer, A. P. Chikkatur, S. Gupta, S. Inouye, T. Rosenband, and W. Ketterle, *Phys. Rev. Lett.* **87**, 130402 (2001)
 - [6] D. Rychtarik, B. Engeser, H.-C. Nägerl, and R. Grimm, *Phys. Rev. Lett.* **92**, 173003 (2004)
 - [7] S. Stock, Z. Hadzibabic, B. Battelier, M. Cheneau, and J. Dalibard, *Phys. Rev. Lett.* **95**, 190403 (2005)
 - [8] N. L. Smith, W. H. Heathcote, G. Hechenblaikner, E. Nugent, and C. J. Foot, *J. Phys. B* **38**, 223 (2005)
 - [9] Z. Hadzibabic, P. Krüger, M. Cheneau, B. Battelier, and J. Dalibard, *Nature (London)* **441**, 1118 (2006)
 - [10] V. Schweikhard, S. Tung, and E. A. Cornell, *Phys. Rev. Lett.* **99**, 030401 (2007)
 - [11] P. Krüger, Z. Hadzibabic, and J. Dalibard, *Phys. Rev. Lett.* **99**, 040402 (2007)
 - [12] Z. Hadzibabic, P. Krüger, M. Cheneau, S. P. Rath, and J. Dalibard, *New Journal of Physics* **10**, 045006 (2008)
 - [13] P. Cladé, C. Ryu, A. Ramanathan, K. Helmerson, and W. D. Phillips, *Phys. Rev. Lett.* **102**, 170401 (2009)
 - [14] S. P. Rath, T. Yefsah, K. J. Günter, M. Cheneau, R. Desbuquois, M. Holzmann, W. Krauth, and J. Dalibard, *Phys. Rev. A* **82**, 013609 (2010)
 - [15] S. Tung, G. Lamporesi, D. Lobser, L. Xia, and E. A. Cornell, *Phys. Rev. Lett.* **105**, 230408 (2010)
 - [16] C.-L. Hung, X. Zhang, N. Gemelke, and C. Chin, *Nature*

- 470**, 236 (2011)
- [17] D. S. Petrov, G. V. Shlyapnikov, and J. T. M. Walraven, *Phys. Rev. Lett.* **87**, 050404 (2001)
 - [18] F. Schreck, L. Khaykovich, K. L. Corwin, G. Ferrari, T. Bourdel, J. Cubizolles, and C. Salomon, *Phys. Rev. Lett.* **87**, 080403 (Aug 2001)
 - [19] S. Dettmer, D. Hellweg, P. Rytty, J. J. Arlt, W. Ertmer, K. Sengstock, D. S. Petrov, G. V. Shlyapnikov, H. Kreutzmann, L. Santos, and M. Lewenstein, *Phys. Rev. Lett.* **87**, 160406 (2001)
 - [20] I. Shvarchuck, C. Buggle, D. S. Petrov, K. Dieckmann, M. Zielonkowski, M. Kemmann, T. G. Tiecke, W. von Klitzing, G. V. Shlyapnikov, and J. T. M. Walraven, *Phys. Rev. Lett.* **89**, 270404 (2002)
 - [21] D. Hellweg, L. Cacciapuoti, M. Kottke, T. Schulte, K. Sengstock, W. Ertmer, and J. J. Arlt, *Phys. Rev. Lett.* **91**, 010406 (2003)
 - [22] S. Richard, F. Gerbier, J. H. Thywissen, M. Hugbart, P. Bouyer, and A. Aspect, *Phys. Rev. Lett.* **91**, 010405 (2003)
 - [23] H. Moritz, T. Stöferle, M. Köhl, and T. Esslinger, *Phys. Rev. Lett.* **91**, 250402 (2003)
 - [24] D. S. Petrov, G. V. Shlyapnikov, and J. T. M. Walraven, *Phys. Rev. Lett.* **85**, 3745 (2000)
 - [25] V. N. Popov, "Functional integrals in quantum field theory and statistical physics," (Reidel, Dordrecht, 1983)
 - [26] V. N. Popov, *Theoretical and Mathematical Physics* **11**, 565 (1972)
 - [27] J. O. Andersen, U. Al Khawaja, and H. T. C. Stoof, *Phys. Rev. Lett.* **88**, 070407 (2002)
 - [28] U. Al Khawaja, J. O. Andersen, N. P. Proukakis, and H. T. C. Stoof, *Phys. Rev. A* **66**, 013615 (2002), erratum: *Phys. Rev. A* **66**, 059902(E) (2002).
 - [29] U. Al Khawaja, N. P. Proukakis, J. O. Andersen, M. W. J. Romans, and H. T. C. Stoof, *Phys. Rev. A* **68**, 043603 (2003)
 - [30] N. P. Proukakis, *Phys. Rev. A* **73**, 023605 (2006)
 - [31] D. L. Luxat and A. Griffin, *Phys. Rev. A* **67**, 043603 (2003)
 - [32] C. Mora and Y. Castin, *Phys. Rev. A* **67**, 053615 (2003)
 - [33] N. M. Bogoliubov, C. Malyshev, R. K. Bullough, and J. Timonen, *Phys. Rev. A* **69**, 023619 (2004)
 - [34] F. Gerbier, *Europhys. Lett.* **66**, 771 (2004)
 - [35] D. Kadio, M. Gajda, and K. Rzążewski, *Phys. Rev. A* **72**, 013607 (2005)
 - [36] F. Gerbier, J. H. Thywissen, S. Richard, M. Hugbart, P. Bouyer, and A. Aspect, *Phys. Rev. A* **67**, 051602 (2003)
 - [37] D. Hellweg, S. Dettmer, P. Rytty, J. Arlt, W. Ertmer, K. Sengstock, D. Petrov, G. Shlyapnikov, H. Kreutzmann, L. Santos, and M. Lewenstein, *Applied Physics B: Lasers and Optics* **73**, 781 (2001)
 - [38] L. Cacciapuoti, D. Hellweg, M. Kottke, T. Schulte, W. Ertmer, J. J. Arlt, K. Sengstock, L. Santos, and M. Lewenstein, *Phys. Rev. A* **68**, 053612 (2003)
 - [39] P. Bouyer, J. H. Thywissen, F. Gerbier, M. Hugbart, S. Richard, J. Retter, and A. Aspect, *J. Phys. IV France* **116**, 219 (2004)
 - [40] M. Hugbart, J. A. Retter, F. Gerbier, A. F. Varón, S. Richard, J. H. Thywissen, D. Clément, P. Bouyer, and A. Aspect, *European Physical Journal D* **35**, 155 (2005), arXiv:cond-mat/0501456
 - [41] T. Schumm, S. Hofferberth, L. M. Andersson, S. Wildermuth, S. Groth, I. Bar-Joseph, J. Schmiedmayer, and P. Krüger, *Nature Physics* **1**, 57 (2005)
 - [42] J.-B. Trebbia, J. Esteve, C. I. Westbrook, and I. Bouchoule, *Phys. Rev. Lett.* **97**, 250403 (2006)
 - [43] J. Estève, J.-B. Trebbia, T. Schumm, A. Aspect, C. I. Westbrook, and I. Bouchoule, *Phys. Rev. Lett.* **96**, 130403 (2006)
 - [44] S. Hofferberth, I. Lesanovsky, B. Fischer, T. Schumm, and J. Schmiedmayer, *Nature (London)* **449**, 324 (2007)
 - [45] A. H. van Amerongen, J. J. P. van Es, P. Wicke, K. V. Kheruntsyan, and N. J. van Druten, *Phys. Rev. Lett.* **100**, 090402 (2008)
 - [46] S. Manz, R. Bücker, T. Betz, C. Koller, S. Hofferberth, I. E. Mazets, A. Imambekov, E. Demler, A. Perrin, J. Schmiedmayer, and T. Schumm, *Phys. Rev. A* **81**, 031610 (2010)
 - [47] T. Betz, S. Manz, R. Bücker, T. Berrada, C. Koller, G. Kazakov, I. E. Mazets, H.-P. Stimming, A. Perrin, T. Schumm, and J. Schmiedmayer, *Phys. Rev. Lett.* **106**, 020407 (2011)
 - [48] P. Krüger, S. Hofferberth, I. E. Mazets, I. Lesanovsky, and J. Schmiedmayer, *Phys. Rev. Lett.* **105**, 265302 (2010)
 - [49] J. Armijo, T. Jacquemin, K. V. Kheruntsyan, and I. Bouchoule, *Phys. Rev. Lett.* **105**, 230402 (2010)
 - [50] Y. Shin, M. Saba, T. A. Pasquini, W. Ketterle, D. E. Pritchard, and A. E. Leanhardt, *Phys. Rev. Lett.* **92**, 050405 (2004)
 - [51] E. A. Hinds, C. J. Vale, and M. G. Boshier, *Phys. Rev. Lett.* **86**, 1462 (2001)
 - [52] W. Hänsel, J. Reichel, P. Hommelhoff, and T. W. Hänsch, *Phys. Rev. A* **64**, 063607 (2001)
 - [53] E. Andersson, T. Calarco, R. Folman, M. Andersson, B. Hessmo, and J. Schmiedmayer, *Phys. Rev. Lett.* **88**, 100401 (2002)
 - [54] Y.-J. Wang, D. Z. Anderson, V. M. Bright, E. A. Cornell, Q. Diot, T. Kishimoto, M. Prentiss, R. A. Saravanan, S. R. Segal, and S. Wu, *Phys. Rev. Lett.* **94**, 090405 (2005)
 - [55] G.-B. Jo, J.-H. Choi, C. A. Christensen, T. A. Pasquini, Y.-R. Lee, W. Ketterle, and D. E. Pritchard, *Phys. Rev. Lett.* **98**, 180401 (2007)
 - [56] *Atom Chips*, edited by J. Reichel and V. Vuletic (Wiley-VCH, Weinheim, Germany, 2011)
 - [57] I. Bloch, T. W. Hänsch, and T. Esslinger, *Phys. Rev. Lett.* **82**, 3008 (1999)
 - [58] F. Gerbier, P. Bouyer, and A. Aspect, *Phys. Rev. Lett.* **86**, 4729 (2001)
 - [59] T. Lahaye, J. M. Vogels, K. J. Günter, Z. Wang, J. Dalibard, and D. Guéry-Odelin, *Phys. Rev. Lett.* **93**, 093003 (2004)
 - [60] W. Guerin, J.-F. Riou, J. P. Gaebler, V. Josse, P. Bouyer, and A. Aspect, *Phys. Rev. Lett.* **97**, 200402 (2006)
 - [61] M. A. Cazalilla, *J. Phys. B* **37**, 48 (2004)
 - [62] Mathilde Hugbart-Fouché (Private Communication).
 - [63] S. P. Cockburn, D. Gallucci, and N. P. Proukakis, *Phys. Rev. A* **84**, 023613 (2011)
 - [64] H. T. C. Stoof, *J. Low Temp. Phys.* **114**, 11 (1999)
 - [65] H. T. C. Stoof and M. J. Bijlsma, *J. Low Temp. Phys.* **124**, 431 (2001)
 - [66] C. W. Gardiner and M. J. Davis, *J. Phys. B* **36**, 4731 (2003)
 - [67] H. T. C. Stoof, in *Dynamics: Models and Kinetic Methods for Non-equilibrium Many Body Sys-*

- tems, NATO ASI Proceedings, Vol. 317, edited by J. Karkheck (Kluwer, Dordrecht, 2000) pp. 491–502, arXiv:cond-mat/9812424
- [68] R. A. Duine and H. T. C. Stoof, Phys. Rev. A **65**, 013603 (2001)
- [69] N. P. Proukakis, Las. Phys. **13**, 527 (2003)
- [70] N. P. Proukakis, J. Schmiedmayer, and H. T. C. Stoof, Phys. Rev. A **73**, 053603 (2006)
- [71] S. P. Cockburn and N. P. Proukakis, Las. Phys. **19**, 558 (2009), arXiv:0812.1926v2
- [72] S. P. Cockburn, H. E. Nistazakis, T. P. Horikis, P. G. Kevrekidis, N. P. Proukakis, and D. J. Frantzeskakis, Phys. Rev. Lett. **104**, 174101 (2010)
- [73] S. P. Cockburn, H. E. Nistazakis, T. P. Horikis, P. G. Kevrekidis, N. P. Proukakis, and D. J. Frantzeskakis, Phys. Rev. A **84**, 043640 (2011)
- [74] S. P. Cockburn, A. Negretti, N. P. Proukakis, and C. Henkel, Phys. Rev. A **83**, 043619 (2011)
- [75] C. N. Weiler, T. W. Neely, D. R. Scherer, A. S. Bradley, M. J. Davis, and B. P. Anderson, Nature **455**, 948 (2008)
- [76] A. S. Bradley, C. W. Gardiner, and M. J. Davis, Phys. Rev. A **77**, 033616 (2008)
- [77] S. J. Rooney, A. S. Bradley, and P. B. Blakie, Phys. Rev. A **81**, 023630 (2010)
- [78] B. Damski and W. H. Zurek, Phys. Rev. Lett. **104**, 160404 (2010)
- [79] N. P. Proukakis and B. Jackson, J. Phys. B **41**, 203002 (2008)
- [80] P. B. Blakie, A. S. Bradley, M. J. Davis, R. J. Ballagh, and C. W. Gardiner, Adv. Phys. **57**, 363 (2008)
- [81] L. Salasnich, A. Parola, and L. Reatto, Phys. Rev. A **65**, 043614 (2002)
- [82] J. N. Fuchs, X. Leyronas, and R. Combescot, Phys. Rev. A **68**, 043610 (2003)
- [83] A. Muñoz Mateo and V. Delgado, Phys. Rev. A **75**, 063610 (2007)
- [84] D. J. Frantzeskakis, J. Phys. A **43**, 213001 (2010)
- [85] Note that the thermal atoms *above* the numerical energy cut-off, which are treated statically here, are not expected to significantly affect the axial modes (due to the relatively lower density of these high energy atoms), thus justifying the approximate form of the interaction term in Eq. (1) (in which n_{\perp} is omitted).
- [86] M. J. Davis, P. B. Blakie, A. H. van Amerongen, N. J. van Druten, and K. V. Kheruntsyan, Phys. Rev. A **85**, 031604 (2012)
- [87] We acknowledge Jocelyn Retter for providing us with the experimental data in 2005.
- [88] Alternatively such a graph may be generated by extracting L from Fig. 3 of [22] and the remaining data from Fig. 3 of [39].
- [89] Specifically, for the modified nonlinearity considered here, we obtain at the Thomas-Fermi radius, $R_{\text{TF}}(T)$, the condition $\mu - V(R_{\text{TF}}(T)) = \hbar\omega_{\perp}(\sqrt{1 + 8a_s n_T} - 1)$ (see also Sec. V B of Ref. [28]). Approximating locally $n_T \approx \langle |\psi|^2 \rangle - n_{\text{qc}}$ in the SGPE generates a Thomas-Fermi radius which is also in excellent agreement with the independent modified Popov prediction.
- [90] N. Prokof'ev, O. Ruebenacker, and B. Svistunov, Phys. Rev. Lett. **87**, 270402 (2001)
- [91] N. P. Proukakis, Phys. Rev. A **74**, 053617 (2006)
- [92] R. N. Bisset, M. J. Davis, T. P. Simula, and P. B. Blakie, Phys. Rev. A **79**, 033626 (2009)
- [93] We should clarify that in our work we use the term ‘quasicondensate’ to refer to the ‘condensate’ component described in [40]
- [94] M. Hugbart-Fouché, *Étude des propriétés de cohérence d'un condensat de Bose-Einstein à l'équilibre et hors équilibre*, Ph.D. Thesis (Université Paris XI, 2010)
- [95] The fractional error in the determination of temperature in Ref. [40] was reported to be in excess of 2.8% [62], while the related preceding work [96] mentions maximum errors in temperature determination in the range of (10-20)%.
- [96] F. Gerbier, J. H. Thywissen, S. Richard, M. Hugbart, P. Bouyer, and A. Aspect, Phys. Rev. A **70**, 013607 (2004)
- [97] The size of the quasicondensate L appearing in Eq. (7) is approximated by the Thomas-Fermi expression $L = \sqrt{2\mu/m\omega_z^2}$ (rather than the *actual* value of L measured in the experiments), where $\mu = \hbar\bar{\omega}/2 (15N_{\text{qc}}a_s/\sqrt{\hbar/(m\bar{\omega})})^{2/5}$ and $\bar{\omega} = (\omega_z \omega_{\perp}^2)^{1/3}$
- [98] The two expressions are reconciled through the relation $n_{\text{qc}}(0) = 15N_{\text{qc}}/16L$ derived by integrating the density profile of a 3D Bose gas confined in an elongated cylindrical harmonic trap over the radial degrees of freedom within the Thomas-Fermi approximation.
- [99] <http://www.cs.wisc.edu/condor>, (2010).
- [100] T. M. Wright, N. P. Proukakis, and M. J. Davis, Phys. Rev. A **84**, 023608 (2011)